

Risk Assessment For
 AR Entertainment's
 Mount Pleasant Way
 Stokesley Business Park
 Stokesley North Yorkshire
 TS9 5NZ

ASSESSMENT UNDERTAKEN
 Date: 29-Mar-17
 Signed..... R D Booth
 Equipment **JUNGLE RUN**

ASSESSMENT REVIEW DATE:
 1st: Sept 2017
 2nd: Mar 2018
 3rd: Sept 2018
 4th: Mar 2019

LIST OF SIGNIFICANT HAZARDS

GROUPS AT RISK

EXISTING CONTROLS covered by information held

Blower/Power Failure	Participants	Operators are instructed to tell participants to remain exactly where they are until the problem is resolved or the inflatable becomes safe to walk off
Overloading	Participants	Operators are instructed to only allow four/six participants on the inflatable at once
Injury caused by boisterous behaviour	Participants	Operators are instructed to segregate older more lively participants from younger less active ones
Collision when exiting the inflatable	Participants Crowd	Inflatable to have an appropriate crowd barrier at a safe distance from the exit
Fire	Participants Crowd/Operator	Operators to site inflatable away from naked flames and forbid smoking on and around the inflatable
Electric shock	Operator	Electrical units are visually inspected for obvious faults, fused Ext. cables are used and equipment is P.A.T. tested once a year
Injury caused by contact with other participants	Participants	Operators instructed to ensure participants, enter 1 or 2 at a time moving in the same direction and only let the next 2 start when the previous participants have gone down the slide feet first. They do not 'jump' down the slide and move away once they are at the bottom. Ensure that nobody tries to climb up the slide the wrong way.
Excessive Wind & Inflatable Tipping Over	Participants Spectators	Operators to site the slide end into the wind. On Grass Check type of soil type under grass - clay has a lot stronger hold than sand Securely double peg all anchor points into the ground. On Hard Standing All supplied weights to be used and anchor to fixed objects if required. If wind speed exceeds 35km/h on windometer or if pegs start to move in the ground or weights start to move when in use, immediately evacuate & deflate until wind has dropped and operator deems appropriate to re-start.

Jungle Run

Safety Data Sheet

Equipment Required

	No req	In van
2 Inflatables	2	
2 x 1.5 Blowers , extension leads, splitter		
Plug converters		
2 x Petrol E blowers, petrol cans & pipe		
2 x Groundsheets		
22 Pegs and hammer		
Sandbags		
Repair kit	1	
Barrow		
Crash Mats		
Map & Key & First aid kit	1+1+1	
Riot fence & stakes		

Assembly Instructions

1. Groundsheet down on required area
2. Unroll Inflatables back from centre of assembly point
Make sure they are positioned as required.
3. Zip up both vents on each inflatable & close deflation tubes
4. Attach blowers and inflate each individually, plug second blower in 30 sec's after first.
5. After inflation join together at the bottom of the bed using velcro flap
6. Still checking they are positioned correctly attach top velcro flap and top buckles
7. Pegdown after fully inflated with all straps slack
8. Place crash mats to cover all open sides

Loading checked by:

Return loading checked by:

Event Manager

Operator Instructions

1. Operator(s), to regulate flow of people at the start, monitor the slide.
When with 2 operators, Preferably at opposite corners so both sides can be supervised at all times.
2. Supervisor to allow second pair access only when first pair reach top of the slide
3. Supervisor to ensure no standing, stopping or jumping from the top of the slide.
4. Make sure participants come feet first down the slide and move quickly off the landing area
5. If a child is at the top of the slide and there is a power failure - tell the child to sit down and the inflatable will slowly deflate to ground level.
6. No footwear, food, drink, cigarettes or sharp objects to be taken on the equipment.
7. Wind Speed should not exceed 35kmh when in use, if so deflate immediately until wind has dropped and operators deem appropriate to re-start

I have read and fully understand the risk assessment, assembly & operating instructions and any other safety procedures in relation to:

Jungle Run

Signed:

Date:

Event Manager/Trainer:

Print name:

Print name: